COMMUNITY WASTE-TO-ENERGY FEASIBILITY IN METRO CEBU

A Thesis Presented to the Faculty of the College of Engineering
Cebu Institute of Technology - University

Grace Lim and Miguel Torres
2023

CHAPTER 1

INTRODUCTION

1.1 Background of the Study

Metro Cebu generates about 1,200 tonnes of municipal solid waste every day, and most of it ends up in the Inayawan and Binaliw landfills. Both sites have repeatedly exceeded their designed capacity since 2019. Local governments have considered waste-to-energy facilities as a way to reduce landfill dependence while producing electricity for the regional grid. However, the feasibility of such facilities depends on the composition, moisture content and calorific value of the waste stream, which no recent study has measured across the metropolitan area.

Earlier assessments relied on national averages published by the Environmental Management Bureau. These averages understate the share of organic and food waste produced by dense urban barangays, and they say nothing about seasonal variation during the wet months. A facility designed on those figures risks operating well below its rated output for a large part of the year.

1.2 Statement of the Problem

This study asks whether a community-scale waste-to-energy facility is technically and financially feasible for Metro Cebu. Specifically, it seeks to determine the composition and calorific value of the waste stream, the conversion technology best suited to that stream, and the capital and operating costs of a small-scale plant. It also asks how sensitive the financial outcome is to the tipping fee charged to local governments.

1.3 Significance of the Study

The findings give local government units a measured basis for procurement decisions that are currently made on borrowed assumptions. They also give the university's

engineering programmes a dataset that later capstone projects can extend. Communities near the landfills benefit indirectly, since any reduction in landfilled volume shortens the time those sites remain open.

CHAPTER 2

REVIEW OF RELATED LITERATURE

2.1 Waste Generation in Metro Cebu

Studies of waste generation in the Visayas report per-capita rates between 0.5 and 0.7 kilograms per day. Urban centres sit at the upper end of that range, and Cebu City has been measured at 0.69 kilograms per person per day. Organic waste makes up roughly half of the total by weight, followed by plastics, paper and residual waste.

Seasonal studies are scarce. The few that exist show the moisture content of mixed waste rising by as much as twelve percentage points during the rainy season, which lowers its heating value considerably.

2.2 Conversion Technologies

Three families of technology dominate the literature: mass-burn incineration, anaerobic digestion and gasification. Mass-burn incineration handles mixed waste with little preparation but requires a high calorific value and costly emission controls. Anaerobic digestion suits wet organic waste and produces biogas at a smaller scale, though it leaves a digestate that must itself be managed.

Gasification converts waste into a synthesis gas that can drive an engine or turbine. Pilot plants in Southeast Asia report frequent shutdowns caused by tar formation when the feedstock is not dried and sorted beforehand. For that reason most reviews treat gasification as unsuited to unsorted municipal waste in humid climates.

Hybrid configurations, in which digestion handles the organic fraction and a small incinerator handles the residual fraction, have been proposed for mid-sized cities. Their economics depend heavily on how reliably the waste can be separated at source.

CHAPTER 3

METHODOLOGY

3.1 Research Design

The study uses a descriptive and evaluative design. Waste characterization establishes the properties of the stream, and a techno-economic model evaluates each candidate technology against those properties. The model is deterministic, and its sensitivity analysis varies one input at a time.

3.2 Data Collection

Waste samples were collected from transfer stations serving four cities over eight weeks, covering both the dry and the wet season. Each sample was sorted by hand into eight categories, weighed, and dried to determine its moisture content. Table 1 summarizes the daily tonnage reported by each city's environment office during the sampling period.

Table 1. Daily municipal solid waste by city (tonnes)

City	Dry season	Wet season
Cebu City	610	655
Mandaue City	240	262
Lapu-Lapu City	205	221
Talisay City	145	151

Calorific value was measured with a bomb calorimeter at the university's chemical engineering laboratory. Three replicates were run for every composite sample, and the mean of the three is reported.

3.3 Data Analysis

Capital and operating costs were estimated from published vendor quotations,

adjusted to 2024 prices. Net present value and the levelized cost of electricity were computed over a twenty-year horizon at a discount rate of ten percent. A plant was judged feasible when its net present value was positive at the median tipping fee charged in the region.

CHAPTER 4

RESULTS AND DISCUSSION

4.1 Waste Composition

Organic waste made up 52 percent of the sampled stream by weight in the dry season and 57 percent in the wet season. Mean moisture content rose from 48 percent to 61 percent between the two seasons. The mean lower heating value of the mixed stream fell below the threshold usually required for self-sustaining combustion during the wet months.

4.2 Feasibility of Each Technology

Mass-burn incineration returned a negative net present value at every tipping fee tested, because supplementary fuel was needed for much of the year. Anaerobic digestion of the separated organic fraction returned a positive net present value at the median tipping fee. The hybrid configuration performed best when source separation exceeded 70 percent, and worst of all when it fell below 40 percent.

CHAPTER 5

CONCLUSIONS AND RECOMMENDATIONS

5.1 Conclusions

A community-scale anaerobic digestion facility is feasible for Metro Cebu if the organic fraction is separated at source. Mass-burn incineration is not feasible given the moisture content measured during the wet season.

5.2 Recommendations

Local governments should strengthen barangay-level source separation before procuring any waste-to-energy facility. Further work should measure the waste stream over a full year and test digestate disposal options.